

**ADDENDUM NO. 1  
TO  
CONTRACT DOCUMENTS, TECHNICAL SPECIFICATIONS, AND DRAWINGS  
FOR  
THE CITY OF WIMBERLEY**

**COLLECTION SYSTEM PROJECT**

TO: PROSPECTIVE OFFERORS AND PLAN HOLDERS

The Contract Documents, Technical Specifications, and Drawings listed below shall be removed in their entirety and replaced with the attached documents to this addendum incorporating the following modifications:

**I. Contract Documents**

1. 00020 Invitation to Bid
  - A. Update Notice paragraph to:  
*"Notice is hereby given that the City of Wimberley (OWNER) will receive sealed Bids at Wimberley City Hall, 221 Stillwater, Wimberley, TX, 78676 until 10:00 a.m. on Wednesday, April 19, 2017 for construction of..."*
  - B. Update Prebid Conference paragraph to:  
*"A non-mandatory prebid conference will be held at the City of Wimberley City Hall (221 Stillwater at 10:30 a.m. on Thursday, March 30, 2017."*
2. 00411 Bid Schedule
  - A. Updated Bid Item No. 17 to include 3 plug valves.
  - B. Added Grinder Pump Station Electrical Allowance.
  - C. Added Service Lateral Allowance.

**II. Technical Specifications**

1. 01302 Supplier's Submittals
  - A. Update references to "Special Conditions" to "General Conditions."
2. 11073 Submersible Grinder Package Pump Stations
  - A. Update paragraph 1.5.A.1 to:  
*"1. The pump manufacturer shall furnish a qualified field representative for a minimum of seven (7) trips and seven (7) working days to inspect all equipment described herein..."*
  - B. Update paragraph 1.5.A.2 to:  
*"2. The pump manufacturer's representative will also hold one (1) maintenance class for the grinder pump station owners/residents to instruct them in routine maintenance and troubleshooting procedures. The class will take place at City Hall."*
  - C. Update paragraph 2.1.4.1.a to include the model number:  
*"a. Environment/One, Model GH30X60"*
  - D. Update paragraph 1.8.A to:  
*"A. Warranty: The grinder pump manufacturer shall provide a part(s) and labor, 100% unconditional warranty on the complete station and accessories, including, but not limited to, control panel and redundant check valve, for a period of twenty-four (24) months after either the date of the City accepted equipment test or thirty-six (36) months after date of delivery of pumps to CONTACTOR, whichever comes first. Manufacturer shall train grinder pump station owners/residents for maintenance to qualify as warranty repair. Provide replacement parts within 10 days of request."*
3. 15020 Piping System, Ductile Iron Pipe
  - A. Section added to project manual.
4. 15030 Piping System, PVC and CPVC Pressure Pipe

- A. Section added to project manual.
- III. **Drawings**
1. G-000 Cover Sheet, Location Map and Index
  2. G-002 General Notes I
    - A. Added note 46 under General Construction Notes:  
*"46. The contractor may bore under roads in lieu of open trench pipe installation at no additional cost to the City."*
    - B. Add the following text to Note 21 under Utility:  
 Collection Gravity PVC (Depth <13 ft): SDR-26  
 Collection Gravity PVC (Depth ≥13 ft): SDR-21  
 Collection Gravity DI (Depth <13 ft): SDR-26  
 Collection Gravity DI (Depth ≥13 ft): SDR-21  
 Collection Force Main PVC: SDR-14  
 Collection Force Main DI: C151 CI 350  
 WW Service Laterals: SDR-26  
 Reclaimed Water PVC: C900 DR 14
  3. G-003 General Notes II
    - A. Delete the following note from the Traffic Notes and Special Conditions:  
 9. Off-duty police officers may be required at no additional cost to the City.
  4. G-004 Gravity Line Site Plan
    - A. Updated to reflect changes to LN A described below.
  5. C-001 and C-002 Gravity LN A
    - A. Sheets reissued; updated alignment of LN A to go around property R18443, HCAD.
  6. C-003, C-004, C-005, C-006, C-007 Gravity LN A; C-008 Gravity LN B; C-023 Gravity LN I; and C-026 Gravity LN J
    - A. Sheets reissued; updated to reflect changes made to alignment of LN A
  7. C-019 Gravity LN E
    - A. Removed manholes E4 and E5.
  8. C-021 Gravity LN G; C-024 Gravity LN I; and C-028 Gravity LN J
    - A. Added references to Sheet C-001, Notes 2 and/or 3.
  9. C-103, C-105, C-108, and C-115 Force Main Plan and Profiles
    - A. Updated all valves on these sheets to plug valves.

All items in conflict with this addendum are hereby deleted.

THIS ADDENDUM IS MADE PART OF THE SPECIFICATIONS AND CONTRACT DOCUMENTS, AND SHALL BE ACKNOWLEDGED ON THE COST PROPOSAL FORM AND ON THE PROPOSAL ENVELOPE.

ALAN PLUMMER ASSOCIATES, INC.  
 TBPE Firm No. 13

*Stephen J. Coonan*

Stephen J. Coonan, P.E.  
 April 7, 2017

